

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION  
FOR  
**PERMANENT PAVEMENT MARKINGS**

RCOC/TS:AL

PAGE 1 OF 1

RCOC20SP811

ORG:11-14-22

REV: 02-09-26

**a. Description.** This work shall be done in accordance with Section 811 of the *Michigan Department of Transportation (MDOT) 2020 Standard Specifications for Construction*, as herein provided.

**b. Materials.** Use materials that meet the requirements of the MDOT 2020 Standard Specifications Section 811.02.

**c. Construction.**

The pavement must be free of excess surface and subsurface moisture that may affect bonding. Heat and apply the sprayable thermoplastic material within the temperature range recommended by the manufacturer.

The Contractor shall apply the sprayable thermoplastic material at an application speed not greater than 16 MPH.

On projects calling for 5,000 feet or less (per color) of sprayable thermoplastic pavement markings to be placed per workday, the Contractor has the option of placing two applications of waterborne paint instead of the sprayable thermoplastic pavement markings when approved in writing by the Engineer. The second application of waterborne is to be completed between 14 and 30 days after the initial application unless otherwise approved by the Engineer.

**d. Measurement and Payment.** The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

<b>Pay Item</b>	<b>Pay Unit</b>
_ Pavt Mrkg, Sprayable Thermopl, _ inch, White, RCOC.....	Foot
_ Pavt Mrkg, Sprayable Thermopl, _ inch, Yellow, RCOC.....	Foot

When two applications of waterborne pavement markings are substituted for a single application of sprayable thermoplastic due to placing 5,000 feet or less (per color) per workday, the two applications of waterborne are paid for as a single application of sprayable thermoplastic under the sprayable thermoplastic pay items in the contract.