

ROAD COMMISSION FOR OAKLAND COUNTY  
SPECIAL PROVISION  
FOR  
**VIDEO TRAFFIC DETECTION CAMERA - REMOVE**

RCOC/TOC

PAGE 1 OF 1

RCOC20SP820S

ORG:05-07-21

REV: 03-01-25

**a. Description**

This work consists of furnishing all labor, equipment, and materials to complete the following work type at location(s) shown on the plans:

1. Remove Video Traffic Detection Camera (of any type) or brand camera which may include Autoscope Camera, AS 2004, AS Solo Pro, AS Solo Terra, AIS IV, Vision, FLIR, ITERIS, etc.
2. Does not include Traffic Monitoring Camera (CCTV) RCOC if separate removal pay item exists on project. Video Traffic Detection Camera, Rem, RCOC pay item may be used if called out on the plans.
3. Does not include Hemispherical Video Detection Camera if separate removal pay item exists on project. Video Traffic Detection Camera, Rem, RCOC pay item may be used if called out on the plans.

This work performed according to the plans and sections 204, 818, 820, 918, and 921 of the Standard Specification for Construction except as herein provided.

**b. Materials**

None specified.

**c. Construction**

Removal of the Video Traffic Detection Camera includes the mounting bracket, fittings, wiring, conduit risers, and all other material necessary to complete the work. Storage or disposal of the removed material will be done as directed by the Engineer and in accordance with section 204 of Standard Specifications for Construction.

**d. Measurement and Payment**

The completed work, as described, will be measured and paid for at the contract unit price using the following pay item(s).

<b>Pay Item</b>	<b>Pay Unit</b>
Video Traf Detection Camera, Rem, RCOC.....	Each

The contract unit price each for **Video Traf Detection Camera, Rem, RCOC (Ea)** shall be payment in full for furnishing all labor to remove the camera (of any type), mounting bracket, fittings, wiring, conduit risers, line hardware, ground rod(s), cable, associated appurtenances, and other material. Material storage or disposal is also included as part of this item and will not be paid for separately. Autoscope cameras, other type cameras, Machine Vision Processors (MVP), and other equipment removed shall be returned to the RCOC at the request of the project engineer. This pay item includes all types of Video Traffic Detection Cameras and Video Traffic Detection Systems as described within this special provision.