

ROAD COMMISSION FOR OAKLAND COUNTY
S.A.D. SPECIAL PROVISION
FOR
FULL WIDTH HMA PAVEMENT CONSTRUCTION

RCOC/SAD:RS

Page 1 of 1

20SAD501D
ORG: 09-17-25

a. Description.

The work shall consist of Hot Mix Asphalt (HMA) construction in accordance with Section 501 of the *2020 Michigan Department of Transportation Standard Specifications for Construction*, as indicated in the contract documents, and as indicated herein.

b. Materials.

All work shall be in accordance with the contract documents.

c. Construction.

1. All work shall be in accordance with the contract documents.
2. Mainline paving shall be paved full width utilizing one paver or the two paver echelon method as appropriate for the proposed pavement widths.

d. Measurement and Payment.

Full width or echelon paving will not be measured and paid for separately but shall be included in the contract unit price for the standard HMA items of work.