

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
CLEARING, RCOC

RCOC/DESIGN:KS/JO

PAGE 1 OF 1

RCOC20SP201B
ORG:02-13-21

a. Description

This work shall be done in accordance with section 201 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction*, except as herein provided.

b. Materials

All work must be in accordance with the contract documents.

c. Construction

Remove trees, stumps, and other vegetation, regardless of size. The removal limits shall extend to 3 feet beyond the proposed grading limit line (slope stake line) or to the right-of-way line, whichever is less, including other areas designated on the plans. Trees are not to be removed until verified by the Engineer. Grading limits include vertical curves at the top of cut sections, toe of fill slopes or as shown on the plans. Trees shall be felled without danger to traffic or injury to other trees, structures or property.

In peat treatment areas, removals shall be to the outside limits of the peat excavation. Between peat excavation limits and outer clearing limits, all vegetation shall be cut off to not more than 6 inches above the ground. Stumps and roots outside the peat excavation limits need not be removed. If approved, stumps may be buried with a minimum cover of two feet in peat disposal areas outside the limits of sound fill.

d. Measurement and Payment

The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Clearing, RCOC.....	Acre
Clearing, RCOC.....	Square Yard

Clearing, RCOC includes all costs for, but not limited to, cutting and removing existing vegetation, trees, stumps; and removing/disposing of all debris as directed by the Engineer.