

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
GRUBBING, RCOC

RCOC/DESIGN:KS/JO

PAGE 1 OF 1

RCOC20SP201C
ORG:02-17-21

a. Description

This work shall be done in accordance with section 201 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction*, except as herein provided.

As a precaution to protect federally protected species, RCOC has removed trees within designated areas within the project. The trees have been removed from the site; however, remaining stumps, woody debris and vegetation have not been removed. Therefore, this work consists of removing the remaining stumps, shrubs, roots, woody debris and other vegetation to the limits shown on the plans necessary to construct the project.

b. Materials

All work must be in accordance with the contract documents.

c. Construction

1. Removals

Completely remove any remaining branches, stumps, woody debris, brush, scrub, and other vegetation, regardless of size.

The removal limits shall extend to 3 feet beyond the proposed grading limit line (slope stake line) or to the right-of-way line, whichever is less, and including other areas designated on the plans. Grading limits include vertical curves at the top of cut sections; toe of fill slopes and as shown on the plans. If approved, stumps may be buried with a minimum cover of two feet in peat disposal areas outside the limits of sound fill.

d. Measurement and Payment

The completed work shall be measured and paid for at the contract unit price for the following pay item:

Pay Item	Pay Unit
Grubbing, RCOC.....	Acre
Grubbing, RCOC.....	Square Yard

Grubbing, RCOC includes all costs for, but not limited to, equipment, labor, materials and disposal of removed materials from the project site.