

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
AGGREGATE BASE, CONDITIONING, RCOC

RCOC/DESIGN:CJ/JO

PAGE 1 OF 1

RCOC20SP302B
ORG:10-27-20

a. Description

This work shall be done in accordance with section 302 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction*, except as herein modified.

Conditioning aggregate base shall be performed after HMA Base Crushing as specified on the project and prior to proposed paving. Conditioning aggregate shall be performed when no additional aggregate base is to be added throughout the project or in station ranges shown on the plans to not receive additional aggregate base.

b. Materials

All work must be in accordance with the contract documents.

c. Construction

Maintenance grading shall be performed as directed by engineer and will not be paid for separately, but shall be considered included regardless of the number of times re-grading is needed.

d. Measurement & Payment

The completed work, including all labor and equipment to perform this work as specified above, shall be measured as shown on the plans and paid for as follows:

Pay Item	Pay Unit
Aggregate Base, Conditioning, RCOC.....	Square Yard

Payment for **Aggregate Base, Conditioning, RCOC** includes loading, hauling, placing and compacting excess crushed base material where it is needed on the project as directed by the Engineer and/or removing and disposing surplus base material from the project. Separate payment will not be made for removing and disposing of excess crushed material and shall be included in the cost of this pay item.

When surplus pulverized material from the project has been exhausted, additional aggregate base material needed to provide the base course cross-section and grade will be paid for separately.