

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
TEMPORARY STORM SEWER BULKHEAD

RCOC/DESIGN:JR/JO

PAGE 1 OF 1

RCOC20SP402B
ORG:03-27-21

a. Description

This work consists of providing, installing, and removing a temporary bulkhead for part-width construction according to the plans and section 402 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction* except as herein provided.

b. Materials

All work must be in accordance with the contract documents.

c. Construction

Install a watertight bulkhead at the end of the proposed pipe ensuring that no water or sediment infiltration will occur after backfilling at locations as identified on the plans. The temporary bulkheads are to be completely removed when extending sewer as directed by the Engineer.

d. Measurement and Payment

Pay Item	Pay Unit
Sewer, Bulkhead, Temp, RCOC.....	Each

Sewer, Bulkhead, Temp, RCOC (Ea) includes equipment, labor and materials to install, locate and remove the temporary sewer bulkhead regardless of size of proposed pipe. **Sewer, Bulkhead, Temp, RCOC** shall only be installed where indicated on the plans. All other locations not identified on the plans where a temporary bulkhead may be necessary will not be paid for separately and will be considered included in other sewer pay items. Proposed storm sewer structures, covers, permanent pipe and backfilling material and operations will be paid for separately. Any damage to the proposed pipe shall be repaired by the Contractor with no additional expense to the owner.