

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
PLANT PRODUCED HOT MIX ASPHALT

RCOC/DESIGN:SH/JOB

PAGE 1 OF 1

RCOC20SP501C

ORG:03-26-21

FHWA: 04-20-21

a. Description

This work shall be done in accordance with section 501 of the *Michigan Department of Transportation (MDOT) 2020 Standard Specifications for Construction* except as follows.

b. Materials

Subsection 501.02.B of the *MDOT 2020 Standard Specifications for Construction* is hereby supplemented with the following:

The plant used in producing the HMA mixture shall have sufficient capacity to maintain a continuous paving operation on the project. If the HMA paving contractor obtains the HMA mixture from a plant other than their own, the paving contractor must have complete control over the plant so that a continuous paving operation can be maintained on the project.

c. Construction

Subsection 501.03.G of the *MDOT 2020 Standard Specifications for Construction* is hereby supplemented with the following:

A small vibratory compactor will be required for areas where conventional rollers will not compact the HMA mixture to the required density.

d. Measurement and Payment

The above items will not be paid for separately and are considered included in the contract unit price for the standard HMA pay items shown on the plans.