

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
POST, FLEXIBLE, DELINEATOR

RCOC/DESIGN:AP/JO

PAGE 1 OF 1

RCOC20SP810A
ORG:04-05-21

a. Description

This work consists of supplying and installing Flexible Delineator Posts as shown on the plans and shall be done in accordance with section 810 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction* except as follows.

b. Materials

Flexible delineator posts shall be yellow and shall be supplied from a manufacturer listed on the MDOT qualified products list, or as approved equal by the Engineer. The length of the post must be sufficient so that when installed, the bottom of the reflective sheeting is 4 feet above the edge of the pavement

Reflective sheeting shall be yellow, ASTM Type XI and shall be supplied from a manufacturer listed on the MDOT qualified products list, or as approved equal by the Engineer. The size of the reflective sheeting must be at least 3 by 9 inches, or 27 square inches.

c. Construction

1. Curb Endings

Flexible delineator posts with reflective sheeting attached shall be installed at all curb endings, as shown on the plans, or directed by the Engineer. Once installed the bottom of the reflective sheeting must be 4 feet above the edge of pavement.

2. Pipe Culvert and Storm Sewer Endings

Drainage Marker posts are to be placed at inlets and outlets of storm sewers and culvert pipes on the approaching traffic side as shown on the plans.

d. Measurement and Payment

The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Post, Flexible, Delineator, RCOC.....	Each

Post, Flexible, Delineator, RCOC includes all labor, equipment and material to complete the work.