

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
RIPRAP, NATURAL STONE

RCOC/DESIGN:AP/JO

PAGE 1 OF 1

RCOC20SP813B
ORG:04-05-21

a. Description

This work consists of the construction of a natural cobble stone riprap per section 813 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction* and as shown on the plans.

b. Materials

All materials shall be natural river cobblestone 12 inch to 24-inch mean diameter with an overall height of 18 inches. A sample of the material and the supply location of the material to be used shall be submitted and approved by the Engineer.

Broken concrete or any other non-natural stone will not be accepted.

c. Construction

Construct and place natural stone riprap in accordance with the requirements for Plain Riprap, under subsection 813.03.E.1, except that final placement thickness shall be as specified above. Individual stone shall be laid with their dimension per plan and as directed by the Engineer.

d. Measurement and Payment

The completed work, as described, will be measured in place and paid for at the contract unit price using the following pay item:

Pay Item	Pay Unit
Riprap, Natural Stone	Square Yard

Riprap, Natural Stone includes all labor, materials, equipment to furnish and place riprap materials to the limits shown on the plans, including the following;

1. Furnishing and installation of Geotextile Liner to the limits of the riprap as shown on the Plans.
2. Provide the Engineer with a sample of the natural stone to be used along with the supply location.