

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
DITCH, PLAIN COBBLE

RCOC/DESIGN:AP/JO

PAGE 1 OF 1

RCOC20SP814B
ORG:04-05-21

a. Description

This work consists of constructing a paved ditch using cobbles underlain with a geotextile liner in accordance with section 814, Paved Ditches, of the *Michigan Department of Transportation 2020 Standard Specifications for Construction*, except as provided herein.

b. Materials

The cobblestones shall consist of natural stone. Crushed concrete shall not be used.

c. Construction

Construct the cobble ditch as specified in section 814.03.

d. Measurement and Payment

The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

Pay Items

Ditch, Plain Cobble, RCOC

Pay Unit

Square Yard

Ditch, Plain Cobble, RCOC will be to the lines and grades as shown on the plans, and includes providing and placing the geotextile liner, excavating and disposing of surplus materials, and shall include all materials, labor and equipment required to complete the work.