

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
CONCRETE SPILLWAY

RCOC/DESIGN:AP/JOB

PAGE 1 OF 1

RCOC20SP802C
ORG:04-05-21

a. Description

This work consists of constructing a concrete spillway in accordance with section 802 of the *Michigan Department of Transportation (MDOT) 2020 Standard Specifications for Construction* and as detailed on the plans, on a prepared base, except as herein provided.

b. Materials

All materials must be in accordance with the contract documents.

c. Construction

Construct the concrete spillway in accordance with subsection 802.3, except 802.3.G Stenciling, of the *MDOT 2020 Standard Specifications for Construction* except as modified by the details on the plans and this special provision. Construct the spillway to ensure a smooth transition of water flow from the concrete curb and gutter flowline to the flowline of the spillway.

d. Measurement and Payment

The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

Pay Item	Pay Unit
Spillway, Conc, RCOC.....	Foot

Spillway, Conc, RCOC includes all equipment, labor and materials to complete this item as specified above. **Spillway, Conc, RCOC** shall be measured along the centerline (flowline) of the spillway as shown in the plans.