

ROAD COMMISSION FOR OAKLAND COUNTY

SPECIAL PROVISION
FOR
HMA GUTTER AND SPILLWAYS

RCOC/DESIGN:AP/JOB

PAGE 1 OF 1

RCOC20SP805A
ORG:04-05-21

a. Description

This work shall be done in accordance with section 814 of the *Michigan Department of Transportation 2020 Standard Specifications for Construction* except as herein provided:

This work shall consist of constructing paved spillways and/or gutters using hot mix asphalt (HMA) as called for on the plans.

b. Materials

HMA material shall be as specified in the HMA Application Estimate, or as otherwise approved by the Engineer. HMA gutter material may be that used in mainline HMA paving if the gutter is placed with mainline top course.

c. Construction

The foundation shall be graded, shaped and compacted to the required cross section and grade. The HMA material shall be placed in one lift and shaped to conform to the detail shown on plan. The HMA material shall be compacted with a vibratory plate compactor or in a manner approved by the engineer.

d. Measurement and Payment

The completed work, as described, will be measured and paid for at the contract unit price using the following pay item(s):

Pay Item	Pay Unit
HMA Gutter.....	Foot
HMA Spillway.....	Foot

HMA Gutter and **HMA Spillway** shall include all necessary labor, equipment and material to construct the HMA Gutter or HMA Spillway.